

Kemper County IGCC – Overview and Operational Summary

Landon Lunsford
September 5, 2017



Agenda



- Major components and unique features
- Process block flow diagram
- Operational summary and statistics
- Remaining technical challenges
- Conclusions
- Next steps



Timeline and Safety

- Project groundbreaking
- Construction begins
- Combined-cycle in service
- First coal feed to gasifier
- Operations suspended
- Total project man-hours
- Total plant man-hours

June 2010

First half of 2011

Third quarter 2014

July 2016

June 28, 2017

41+ MM

Recordable Incident Rate (RIR) = 0.42

~2.5 MM


RIR = 0.16

Kemper County IGCC Overview




- Mine-mouth lignite
- **2x1 IGCC**
 - Two Transport Gasifiers (TRIG™)
 - Two Siemens SGT6 - 5000F CTs
 - One Toshiba steam turbine
 - 65+% carbon capture
~800 lb_{CO2}/MWh_{net} or ~550 lb_{CO2}/MWh_{gross}
 - 582 MW peak and 526 MW on syngas
 - Heat rate 12,150 Btu/kWh_{NET}
- **Byproducts (TPY)**
 - ~3,800,000 - CO₂ used for EOR
 - ~150,000 - sulfuric acid
 - ~19,000 – ammonia

Kemper Lignite Composition				
		Average	Min	Max
Heat Content	btu/lb	5,290	4,765	5,870
Moisture	%	45.5	42	50
Ash	%	12.0	8.6	17
Sulfur	%	1.0	0.35	1.7



Kemper Project Map

- ~70 miles transmission
- ~60 miles CO₂ pipeline (for EOR)
- ~5 miles natural gas pipeline
- ~30 miles treated effluent line




Kemper Block Flow Diagram



Patented by Southern
Company

Tested at PSDF
(Commercially Available)

Not Tested at PSDF
(Commercially Available)




Operational Summary




- Achieved fully integrated operation of entire IGCC
 - Both CTs produced power with syngas
 - Steam turbine produced power with superheated steam from the syngas coolers
 - On spec production of byproducts – CO₂, anhydrous ammonia, sulfuric acid
- First-of-a-kind commercial TRIG™ gasification system
 - Availability as good or better than other gasification technologies during first year operation
 - 90% gasifier availability
- Availability following expected availability ramp
- Kemper operation suspended primarily due to dramatic decrease in price and forecast for natural gas
 - Natural gas prices and forecast decreased 60-70% since 2010 project approval

Coal IGCC Plant Syngas Production Availabilities





Coal IGCC Plant Syngas Production Availabilities



TRIG Advantages

- No internal burners / fuel injectors
- Longer refractory life
- Dry ash – no molten slag or corrosive / erosive blackwater system
- Higher carbon conversion → less tar → less syngas cooler fouling

Key Operating Statistics




- Gasifier operation
 - 224 total days of lignite gasification
 - Achieved 100% gasifier design coal feed capacity
- Syngas cleanup/emissions
 - Met all environmental permit requirements
 - Achieved design 65% CO₂ capture and transport for Enhanced Oil Recovery (EOR)
 - On spec production of CO₂, ammonia and sulfuric acid
- CT operation on syngas
 - 73% capacity achieved at 170 MW
 - *Siemens limited CT capacity on syngas to 70% until June 2017, then increased to 80%*
 - 164,900 MWh generated with syngas

Remaining Challenges



Inconsistent raw coal quality

- Frequently outside design range for both moisture and particle size
- Modifications in May-June 2017 improved reliability
- Before modifications, sustained 80% gasifier coal feed capacity with three dryers
- After modifications, sustained 80% gasifier coal feed capacity with two dryers.
- Additional changes were being developed and implemented




Kemper Lignite Composition				
		Average	Min	Max
Heat Content	btu/lb	5,290	4,765	5,870
Moisture	%	45.5	42	50
Ash	%	12.0	8.6	17
Sulfur	%	1.0	0.35	1.7

Remaining Challenges

Refractory replacement in the gasifier seal leg outlet

- Refractory improperly installed in shop - experienced significant and uncharacteristic spalling during drying, but construction schedule prevented refractory replacement
- Bottom sections replaced in situ during commissioning and worked well thereafter
- Upper section spalled from the seal leg, blocking ash removal and requiring periodic clean-out
- Refractory replacement scheduled for upcoming October 2017 outage would have eliminated significant spalling




Remaining Challenges



Syngas cooler superheater tube leaks

- Numerous leaks developed at tube supports of Coil 5 on multiple superheaters
- Finite element analysis revealed insufficient tube thickness/design margin at tube support weld connections
- All Coil 5 tubes plugged in each train's Superheater II prior to June 2017
 - Sufficient heat transfer area remaining for full coal feed rates because less tube fouling than expected
 - Inner coils likely under less overall stress than Coil 5 per engineering evaluations
- No additional tube failures, but insufficient operating time to prove conclusively reliable



Remaining Challenges

Excess sour water production from syngas scrubbers


- Damage to scrubber internals and design of chimney trays allowed excessive water bypassing to sour water system
- Sour water system overwhelmed with two gasifier trains at higher coal feed rates
- Chimney tray redesign scheduled for October outage would have resolved this issue



Remaining Challenges

Salt formation in the Sour Water system

- High sour water pH preventing adequate separation of ammonia, CO_2 and H_2S
- Ammonium bisulfide salts forming in ammonia purification equipment, limiting capacity and reliability at high coal feed rates
- Acid and caustic injection changes in progress to increase pH control and improve separation



Conclusions



- Core TRIG™ technology successfully demonstrated at commercial scale
 - Operated at 100% of coal feed design
 - Produced syngas suitable for power generation in the CT
- Kemper IGCC demonstrated with dual-train operation
 - Modifications required to sustain operation of both trains simultaneously and to achieve the long-term availability ramp
- Fuel price differential between natural gas and lignite was the primary reason for suspension of operations prior to making the identified modifications for sustained dual-train operation

Next Steps



- Evaluate and develop best practices and lessons learned from design, construction, startup and operations of the Kemper IGCC project
- Continue supporting DOE mission to advance clean coal and carbon capture technologies
 - Commissioning report with lessons learned
 - Final Full Project report with lessons learned
 - TRIG™ reference plant with expected capital and operating costs for next-generation TRIG™ IGCC
- Continue supporting development of clean coal technologies to ensure they are ready to serve energy needs where fuel costs and carbon capture credits make them economically competitive

Questions?

